Prepared by and return to: The Story county Engineer's Office, 837 N Ave, Nevada Iowa 50201 Phone515-382-7355

RESOLUTION #20-72

Story County Board of Supervisors

Award of Bid for Projects L-LIN20—73-85 and L-C26—73-85

Bridge Replacement Projects on 690th Ave. in Section 20-85-21 and on 720th Ave; over a small stream on the west line of section 26 of T82N-R21W

BE IT RESOLVED, by the Story County Board of Supervisors, as follows:

Section 1: That bid for L-LIN20—73-85 and L-C26—73-85 be awarded to the low bidder, PROGRESSIVE STRUCTURES, LLC, ELKADER, IA for the total cost of $222,013.65.

Section 2: That the chair be authorized to sign the contract documents on behalf of the board.

Section 3: That this resolution shall take effect immediately.

Adopted this 03rd day of March, 2020

Recommended Approval by:

Darren Moon 2-27-20

Darren R Moon, P.E. Date
County Engineer

_____ Attest:_____

Chair, Board of Supervisors County Auditor

ROLL CALL FOR ALLOWANCE	Lauris Olson	Yea ___	Nay ___	Absent ___
	Lisa Heddens	Yea ___	Nay ___	Absent ___
	Linda Murken	Yea ___	Nay ___	Absent ___
ALLOWED BY VOTE OF THE BOARD		Yea ___	Nay ___	Absent ___

_____ Above tabulation made by _____

CHAIRPERSON

Story County
Secondary Road Letting

Project Number L-LIN20--73-85 - 690TH AVE. Bridge Replacement - Twin Box				Engineers Estimate		PROGRESSIVE STRUCTURES, LLC ELKADER, IA		PETERSON CONTRACTORS INC., REINBECK, IA		REILLY CONSTRUCTION CO., INC., OSSIAN, IA	
No.	Item	Quantity	Unit	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
1	CLEARING AND GRUBBING	0.50	ACRE	$ 2,000.00	$1,000.00						
2	EXCAVATION, CLASS 10, ROADWAY AND BORROW	254.00	CY	$ 11.00	$2,794.00						
3	EXCAVATION, CLASS 10, CHANNEL	46.70	CY	$ 15.00	$700.50						
4	REMOVAL OF EXISTING BRIDGE	1.00	LS	$ 6,000.00	$6,000.00						
5	EXCAVATION, CLASS 20	239.00	CY	$ 20.00	$4,780.00						
6	PRECAST CONCRETE BOX CULVERT,TWIN 12'X8'	42.00	LF	$ 2,000.00	$84,000.00						
7	PRECAST CONCRETE BOX CULVERT STRAIGHT END SECTION,TWIN 12'X8'	2.00	EACH	$ 25,000.00	$50,000.00						
8	ENGINEERING FABRIC	113.80	SY	$ 6.00	$682.80						
9	REVETMENT, CLASS E	66.00	TON	$ 60.00	$3,960.00						
10	SAFETY CLOSURE	4.00	EACH	$ 150.00	$600.00						
11	TRAFFIC CONTROL	1.00	LS	$ 2,500.00	$2,500.00						
12	MOBILIZATION	1.00	LS	$ 6,500.00	$6,500.00						
13	REMOVAL OF EXISTING BROKEN CONCRETE REVETMENT	37.40	CY	$ 50.00	$1,870.00						
				Subtotal =	$165,387.30	Subtotal =	$145,892.50	Subtotal =	$156,832.25	Subtotal =	$171,593.40

Project Number L-C26--73-85 - 720TH AVE. Bridge Replacement - RCB culvert				Engineers Estimate		PROGRESSIVE STRUCTURES, LLC ELKADER, IA		PETERSON CONTRACTORS INC., REINBECK, IA		REILLY CONSTRUCTION CO., INC., OSSIAN, IA	
No.	Item	Quantity	Unit	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
1	CLEARING AND GRUBBING	0.3	ACRE	$ 3,000.00	$900.00						
2	EXCAVATION, CLASS 10, ROADWAY AND BORROW	189.00	CY	$ 11.00	$2,079.00						
3	EXCAVATION, CLASS 10, CHANNEL	14.00	CY	$ 15.00	$210.00						
4	REMOVAL OF EXISTING BRIDGE	1.00	LS	$ 6,000.00	$6,000.00						
5	REMOVALS, AS PER PLAN	1.00	LS	$ 3,500.00	$3,500.00						
6	EXCAVATION, CLASS 20	86.00	CY	$ 20.00	$1,720.00						
7	PRECAST CONCRETE BOX CULVERT, 12'x6'	42.00	LF	$ 1,500.00	$63,000.00						
8	PRECAST CONCRETE BOX CULVERT STRAIGHT END SECTION, 12'x6'	1.00	EACH	$ 18,000.00	$18,000.00						
9	ENGINEERING FABRIC	53.30	SY	$ 6.00	$319.80						
10	REVETMENT, CLASS E	46.70	TON	$ 60.00	$2,802.00						
11	SAFETY CLOSURE	4.00	EACH	$ 150.00	$600.00						
12	TRAFFIC CONTROL	1.00	LS	$ 2,500.00	$2,500.00						
13	MOBILIZATION	1.00	LS	$ 6,500.00	$6,500.00						
14	REVETMENT, REMOVE STOCKPILE AND DISPOSE	63.30	CY	$ 50.00	$3,165.00						
				Subtotal =	$111,295.80	Subtotal =	$76,121.15	Subtotal =	$76,675.90	Subtotal =	$84,403.00

Total =	$276,683.10	Total =	$222,013.65	Total =	$233,508.15	Total =	$255,996.40

Recommend Award To: PROGRESSIVE STRUCTURES, LLC